

TILT-UP AND PRECAST

COP = Code of Practice

Work at Heights	
<ul style="list-style-type: none">- Work Health & Safety Regulation: s78-80, s306c-306j- Managing the Risk of Falls at Workplaces COP 2011- Scaffolding COP 2009	<ul style="list-style-type: none">• Risk assessment for work at height less than 2m.• Controls in place if risk of fall more than 2m (e.g. edge protection).• Adequate work platforms provided and used e.g. EWP, mobile scaffolding.• No gaps in perimeter edge protection, if used<ul style="list-style-type: none">• Penetrations covered/secured
Falling Objects	
<ul style="list-style-type: none">- Work Health & Safety Regulation 2011: s315b-315m- Managing the Risk of Falls at Workplaces COP 2011	<ul style="list-style-type: none">• Access to work area restricted to persons directly involved in erecting panels when lifting taking place.• Exclusion zone maintained during panel lifting until braces secured and lifting slings removed.• Controls implemented for loads being lifted over adjoining areas e.g. adjoining area closed/gantry erected.
Electrical	
<ul style="list-style-type: none">- Electrical Safety Regulation 2002: s87- Tilt Up and Pre-Cast Construction COP 2003- Working Near Exposed Live Parts COP	<ul style="list-style-type: none">• Electrical equipment kept away from water.• Safety Switch installed on supply switchboard.• Extension leads secured and protected from damage.• Testing and tagging current (every 3 months).• Exclusion zone for workers and plant of 3 m around live overhead power lines (6-8m for high voltage lines).• Safety observer present when crane/plant could enter into exclusion zone.
Safe Access & Housekeeping	
<ul style="list-style-type: none">- Work Health & Safety Regulation 2011: s40- Work Health & Safety Act 2011: s19	<ul style="list-style-type: none">• Working area kept clear and tidy.• Trip hazards managed e.g. material neatly stacked.• Waste material put in designated area / bin / skip.
Manual Tasks	
<ul style="list-style-type: none">- Work Health & Safety Regulation 2011: s60- Work Health & Safety Act 2011: s19- Hazardous Manual Tasks COP 2011	<ul style="list-style-type: none">• High risk manual tasks identified e.g. continuous heavy lifting, excessive pulling/pushing movements.• Controls implemented for high risk manual tasks eg use mechanical aids / cranes.
Noise	
<ul style="list-style-type: none">- Work Health & Safety Regulation 2011: s56 - 58- Work Health & Safety Act 2011: s19- Managing Noise and Preventing Hearing Loss at Work COP 2011	<ul style="list-style-type: none">• Controls implemented to minimise exposure e.g. hearing protection

Amenities	
<p>- Work Health & Safety Regulation 2011: s40, s41, s315A, Schedule 5A Part 2 (3), Part 3 (5)(2), Part 3 (7)</p> <p>- Managing the Work Environment and Facilities COP 2011</p>	<p>Meal areas:</p> <ul style="list-style-type: none"> • a room or sheltered area. <p>Toilets:</p> <ul style="list-style-type: none"> • reasonable access to one toilet for each 15 workers. <p>Washing facilities:</p> <ul style="list-style-type: none"> • separate from toilets. <p>Drinking water:</p> <ul style="list-style-type: none"> • from a source other than toilet, hand or washing facilities. <p>First aid:</p> <ul style="list-style-type: none"> • reasonable access to appropriate and adequate first aid facilities.
PPE	
<p>- Work Health & Safety Regulation 2011: Work Health & Safety Regulation 2011</p>	<ul style="list-style-type: none"> • Workers wearing steel capped boots, sun protection (eg hard hat with shade brim, shirts, sunglasses)



www.qld.cfmeu.asn.au
 ABN: 24 502 631 846